



AshGridX Pilot Integration

Technical clarification acknowledgement and next-step request

TO	AshGridX Technical and Pilot Support Team	DATE	17 August 2026
SUBJECT	BuiltRight pilot integration - clarification acknowledgement and next steps	FROM	BuiltRight Services Ltd

Dear Israel,

Thank you for the detailed technical clarification. We have reviewed the responses and are ready to proceed with the BuiltRight pilot integration.

Our understanding of the confirmed AshGridX behavior is summarized below.

Device identity

BuiltRight will use **deviceNumber** as the primary identifier for every customer device. AshGridX will generate **customerDeviceId** during onboarding.

Control behavior

A successful control response confirms that the request was accepted. BuiltRight will verify the actual state through the status endpoint. Offline commands are not queued.

Protection and tamper

A cable disconnection triggers a BYPASS/protection event and physically shuts down the inverter. Webhook delivery may take up to five minutes.

Webhook security

Webhooks will use HMAC-SHA256 verification with a 120-second timestamp tolerance. Protection removal is a separate operation requiring its own authorization key.

Pilot activation requirements

To begin the pilot, please provide the following items:

- Pilot device purchase and onboarding instructions.
- Staging API base URL and API key.
- Webhook secret and the exact signature and timestamp header names.
- Required IP-whitelisting details.
- Device onboarding and assignment procedure.
- Complete staging API documentation, including status, control, protection-history, and device-management endpoints.
- Sample signed webhook payloads for BYPASS, restoration, online, and offline events.
- AshGridX pilot testing checklist and acceptance criteria.
- Confirmation of the support process during installation and testing.

BuiltRight implementation and test approach

BuiltRight will map each customer to a unique deviceNumber, test tamper alerts, verify device state changes, and maintain a complete command and event audit trail.

Remote control will remain disabled until staging tests are successfully completed and approved by both parties.

01	Onboard Purchase and register the first pilot device through the AshGridX dashboard.
02	Connect Configure the staging credentials, webhook secret, callback URL, and any required IP whitelist.
03	Map Assign the AshGridX customerDeviceId to the BuiltRight deviceNumber and customer record.
04	Test Run signed BYPASS, restoration, online, offline, status, and control-state tests.
05	Approve Review the audit trail and jointly approve the pilot before enabling live control.

Please let us know the next step for purchasing and onboarding the first pilot device.

Kind regards,

BuiltRight Services Ltd
Operations and Technical Integration Team

BuiltRight Services Ltd | Lagos, Nigeria | builtrightltd.com